STRUCTURAL BEAM DETAILS AT 1ST BASEMENT FLOOR LEVEL.

BEAM DETAIL AT 1ST BASEMENT FLOOR LVL

BEAM NO.	SIZE	TOP R/F			BOTTOM R/F		STIRRUPS			REMARKS
		THROUGH	EXTRA LEFT	EXTRA RIGHT	THROUGH	EXTRA MID	LEFT	MID	RIGHT	
B1	300X600	3-T16	-	-	3-T16	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	-
B2a	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@125C/C(ALL)	T8@150C/C(ALL)	T8@125C/C(ALL)	REBARING IN D-WALL
B2b	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B2c	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B2d	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@150C/C(ALL)	T8@150C/C(ALL)	T8@150C/C(ALL)	-
B2e	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@150C/C(ALL)	T8@150C/C(ALL)	T8@150C/C(ALL)	-
B2f	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@150C/C(ALL)	T8@150C/C(ALL)	T8@150C/C(ALL)	-
B2g	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B2h	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@125C/C(ALL)	T8@150C/C(ALL)	T8@125C/C(ALL)	REBARING IN D-WALL
B3a	300X600	3-T16	-	2-T20+1-T16	3-T16	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	REBARING IN D-WALL
B3b	300X600	3-T16	2-T20+1-T16	2-T20+1-T16	3-T20	2-T20+1-T25 (ALL)	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	3-T16 STOP&3-T20 START.
B3c	300X600	3-T16	2-T20+1-T16	-	3-T16	-	T10@125C/C(ALL)	T10@175C/C(ALL)	T10@125C/C(ALL)	3-T20 STOP & 3-T16 START
B3d	300X600	3-T16	-	-	3-T16	-	T8@100C/C(ALL)	T8@125C/C(ALL)	T8@100C/C(ALL)	-
B3e	300X600	3-T16	-	2-T12	3-T16	-	T8@100C/C(ALL)	T8@125C/C(ALL)	T8@100C/C(ALL)	-
B3f	300X600	3-T16	2-T12	-	3-T16	2-T16	T10@125C/C(ALL)	T10@150C/C(ALL)	T10@125C/C(ALL)	REBARING IN D-WALL
B4a	230X600	2-T16+1-T12		2-T12	2-T16+1-T12	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	REBARING IN D-WALL
B4b	230X600	2-T16+1-T12	2-T12	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B4c	230X600	2-T16+1-T12	-	2-T12	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B4d	230X600	2-T16+1-T12	2-T12	-	2-T16+1-T12	-	T8@125C/C(ALL)	T8@150C/C(ALL)	T8@125C/C(ALL)	-
B4e	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@150C/C(ALL)	T8@150C/C(ALL)	T8@150C/C(ALL)	-
B4f	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@150C/C(ALL)	T8@150C/C(ALL)	T8@150C/C(ALL)	-
B4g	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B4h	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	REBARING IN D-WALL
B5	300X600	3-T16	-	2-T12	3-T16	2-T12	T10@100C/C(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	REBARING IN D-WALL
B6a	300X600	2-T20+1-T16	3-T16	3-T16	3-T20	2-T25+1-T20 (ALL)	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B6b	300X600	2-T20+1-T16	3-T16	-	3-T20	-	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	3-T20 STOP & 3-T16 START
B6c	300X600	2-T20+1-T16	-	-	3-T20	-	T10@100C/C(ALL)	T10@150C/C(ALL)	T10@100C/C(ALL)	-
B6d	300X600	2-T20+1-T16	-	2-T16	3-T20	-	T10@100C/C(ALL)	T10@150C/C(ALL)	T10@100C/C(ALL)	-
B6e	300X600	2-T20+1-T16	2-T16	-	3-T20	2-T12	T10-3L@125C/C(ALL)	T10@100C/C(ALL)	T10-3L@125C/C(ALL)	REBARING IN D-WALL
B7	300X600	2-T20+1-T16	2-T16+1-T20	2-T20+1-T16	3-T20	2-T25+1-T20 (ALL)	T10-3L@125C/C(ALL)	T10@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B8a	300X600	3-T20	-	2-T16+1-T20	2-T20+1-T25	2-T20	T10-3L@125C/C(ALL)	T10@100C/C(ALL)	T10-3L@125C/C(ALL)	REBARING IN D-WALL
B8b	300X600	3-T20	2-T16+1-T20	-	2-T20+1-T25	2-T20	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B8c	300X600	3-T20	-	2-T20+1-T25	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B8d	300X600	3-T20	2-T20+1-T25	3-T20	2-T20+1-T25	3-T25(ALL)	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B8e	230X600	3-T20	3-T20	2-T16	2-T20+1-T25	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	-
B8f	300X600	3-T20	2-T16	2-T16	2-T20+1-T25	2-T20	T10-3L@125C/C(ALL)	T10@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B8g	230X600	3-T20	2-T16	3-T20	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B8h	300X600	3-T20	3-T20	2-T20+1-T25	2-T20+1-T25	3-T25(ALL)	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B8i	300X600	3-T20	2-T20+1-T25	-	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B8j	300X600	3-T20	-	2-T16	2-T20+1-T25	2-T20	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B8k	300X600	3-T20	2-T16	-	2-T20+1-T25	2-T20	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B9a	300X600	3-T20	2-T16	2-T16	2-T20+1-T25	2-T20	T10@100C/C(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	-
B9b	300X600	3-T20	2-T16	2-T16	2-T20+1-T25	2-T16	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B9c	300X600	3-T20	2-T16	2-T20+1-T25	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-

*BEAMS THOSE HAVING SPAN MORE THAN 6.5M, MUST BE CAMBER BY 20MM FROM THE CENTER POINT OF BEAM

*BEAMS THOSE HAVING SPAN MORE THAN 6.5M, MUST BE CAMBER BY 20MM FROM THE CENTER POINT OF BEAM

STRUCTURAL BEAM DETAILS AT 1ST BASEMENT FLOOR LEVEL.

BEAM DETAIL AT 1ST BASEMENT FLOOR LVL

BEAM NO.	SIZE	TOP R/F			BOTTOM R/F		STIRRUPS			REMARKS
		THROUGH	EXTRA LEFT	EXTRA RIGHT	THROUGH	EXTRA MID	LEFT	MID	RIGHT	
B9d	300X600	3-T20	2-T20+1-T25	2-T20+1-T25	2-T20+1-T25	3-T25(ALL)	T10-3L@125C/C(ALL)	T10@100C/C(ALL)	T10-3L@125C/C(ALL)	-
B9e	300X600	3-T20	2-T20+1-T25	2-T16	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B9f	300X600	3-T20	2-T16	2-T16	2-T20+1-T25	2-T16	T10@100C/C(ALL)	T8@100C/C(ALL)	T10@100C/C(ALL)	-
B9g	300X600	3-T20	2-T16	3-T16	2-T20+1-T25	-	T10@100C/C(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	-
B9h	300X600	3-T20	3-T16	2-T16	2-T20+1-T25	2-T20+1-T16 (ALL)	T10-3L@125C/C(ALL)	T10@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B9i	300X600	3-T20	2-T16	2-T16	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B9j	300X600	3-T20	2-T16	2-T20+1-T16	2-T20+1-T25	2-T20	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B9k	300X600	3-T20	2-T20+1-T16	-	2-T20+1-T25	2-T16	T10-3L@125" C/C(ALL)	T10-3L@150C/C(ALL)	T10-3L@125C/C(ALL)	REBARING IN D-WALL
B10a	300X600	2-T20+1-T16	-	2-T20+1-T16	2-T20+1-T25	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B10b	300X600	2-T20+1-T16	2-T20+1-T16	2-T20+1-T16	2-T20+1-T25	3-T20(ALL)	T10-3L@100C/C(ALL)	T10-3L@100C/C(ALL)	T10-3L@100C/C(ALL)	STUB (SC1) START.
B11	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B12a	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B12b	300X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B12c	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B13a	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B13b	300X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B14a	300X600	3-T16	2-T16+1-T20	2-T16+1-T20	3-T20	2-T20+1-T25	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B14b	300X600	3-T16	2-T16+1-T20	2-T16	3-T20	2-T16	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B15a	300X600	3-T20	-	2-T16	3-T20	2-T16	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	REBARING IN D-WALL
B15b	300X600	3-T20	2-T16	-	3-T20	2-T12	T10@125C/C(ALL)	T10@150C/C(ALL)	T10@125C/C(ALL)	-
B15c	300X600	3-T20	-	3-T16	3-T20	-	T10@100C/C(ALL)	T10@150C/C(ALL)	T10@100C/C(ALL)	-
B15d	300X600	3-T20	3-T16	3-T16	3-T20	2-T20+1-T25 (ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	-
B15e	230X600	3-T20	3-T16	-	3-T20	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B15f	230X600	3-T20	-	-	3-T20	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	-
B15g	230X600	3-T20	-	3-T16	3-T20	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B15h	300X600	3-T20	3-T16	3-T16	3-T20	2-T20+1-T25 (ALL)	T10-3L@125C/C(ALL)	T10-3L@150C/C(ALL)	T10-3L@125C/C(ALL)	-
B15i	300X600	3-T20	3-T16	-	3-T20	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B15j	300X600	3-T20	-	2-T16	3-T20	2-T12	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B15k	300X600	3-T20	2-T16	-	3-T20	2-T16	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	-
B16a	300X600	2-T20+1-T16	-	-	3-T20	-	T10@125C/C(ALL)	T10@150C/C(ALL)	T10@125C/C(ALL)	-
B16b	300X600	2-T20+1-T16	-	2-T20+1-T16	3-T20	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B16c	300X600	2-T20+1-T16	2-T20+1-T16	2-T20+1-T16	3-T20	2-T20+1-T25 (ALL)	T10-3L@125C/C(ALL)	T10@100C/C(ALL)	T10-3L@125C/C(ALL)	-
B16d	230X600	2-T20+1-T16	2-T20+1-T16	-	3-T20	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B16e	230X600	2-T20+1-T16	-	-	3-T20	-	T8@125C/C(ALL)	T8@125C/C(ALL)	T8@125C/C(ALL)	-
B16f	230X600	2-T20+1-T16	-	3-T25	3-T20	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B16g	300X600	2-T20+1-T16	3-T25	2-T20+1-T25	3-T20	3-T25(ALL)	T10-3L@100C/C(ALL)	T10-3L@100C/C(ALL)	T10-3L@100C/C(ALL)	STUB (SC1) START.
B16h	300X600	2-T20+1-T16	2-T20+1-T25	-	3-T20	-	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	T10-3L@125C/C(ALL)	-
B16i	300X600	2-T20+1-T16	-	3-T16	3-T20	2-T16	T10@125C/C(ALL)	T10@150C/C(ALL)	T10@125C/C(ALL)	-
B16j	300X600	2-T20+1-T16	3-T16	-	3-T20	2-T16	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	REBARING IN D-WALL
B17a	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B17b	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B17c	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-
B17d	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B17e	230X600	2-T16+1-T12	-	-	2-T16+1-T12	-	T10@125C/C(ALL)	T10@125C/C(ALL)	T10@125C/C(ALL)	-
B18a	300X600	3-T16	-	2-T16+1-T20	3-T16	3-T16(ALL)	T10@100C/C(ALL)	T10@125C/C(ALL)	T10@100C/C(ALL)	REBARING IN D-WALL
B18b	300X600	3-T16	2-T16+1-T20	-	3-T16	2-T16(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	T10@100C/C(ALL)	-
B18c	300X600	3-T16	-	-	3-T16	-	T8@100C/C(ALL)	T8@100C/C(ALL)	T8@100C/C(ALL)	-

*BEAMS THOSE HAVING SPAN MORE THAN 6.5M, MUST BE CAMBER BY 20MM FROM THE CENTER POINT OF BEAM

1. ALL DIMENSIONS AND LEVELS ARE IN MM.
2. T – INDICATES TMT HIGH YIELD STRENGTH DEFORMED BARS CONFIRMING TO IS:1786 OR EQUIVALENT WITH 0.2% PROOF STRESS OF 550 N/mm².
3. ALL DIMENSIONS & LEVELS SHALL BE CHECKED WITH ARCHITECTURAL DRAWINGS. ANY AMBIGUITY, IF FOUND, SHALL BE BROUGHT TO THE NOTICE
4. OF THE CONSULTANTS BEFORE EXECUTION OF THE WORK.
5. SUPERVISION SHALL NOT BE OUR RESPONSIBILITY.
6. CURING OF CONCRETE MEMBERS SHALL BE CARRIED OUT FOR A MINIMUM PERIOD OF 12 DAYS AFTER CASTING BY PONDING OR COVERING SURFACE BY JUTE BAGS KEPT CONSTANTLY WET OR SUCH OTHER MEANS.
7. CONTRACTOR SHALL TAKE CARE OF ALL UNDER GROUND UTILITIES OF CIVIL, MECHANICAL, ELECTRICAL AND OTHER SERVICES AS THEY
8. INTERFACE WITH STRUCTURAL FOUNDATIONS AND OTHER UNDERGROUND WORKS.
9. SAND/EARTH FILLING SHALL BE DONE SIMULTANEOUSLY BOTH SIDE OF WALL.
10. LAP LENGTH SHALL BE 50 TIMES DIA. OF BARS.

KEY PLAN



GOOD FOR CONSTRUCTION
ISSUED ON DATE:19/03/2025

GRADE OF CONCRETE MIX= M35
GRADE OF STEEL= FE550D

PRINTS ISSUED

DATE	REV.	ARCH	CLIENT	SITE	CONSL.	CONTR.	OFFICE	TOTAL	REMARK
19.03.2025	R0	MAIL	–	–	–	–	01	01	GFC.

NO	DATE	REVISION	BY	DR	CH

ARCHITECT :

mansi shah ARCHITECTS

JOB TITLE
TROGON CENTRE COURT

DRAWING TITLE
STRUCTURAL BEAM DETAIL AT 1ST BASEMENT LVL.

JOB NO	DATE	SHEET SIZE	SCALE
2207023	19.03.2025	A0	1:73

DRG. NO.	REVISION	DRAWN	DESIGN	CHECKED
S-302	R0	RSS	RS/KN	NKP

STRUCTURAL CONSULTANT

HNBS

HNBS DESIGN STUDIO

1007, TIMES SQUARE ARCADE 1,
NEAR RAVIJA PLAZA,OPPOSITE
RAMBAG,THALTEJ,SHILAJ,
AHMEDABAD, 380059,
E mail: contact@hnbs.co.in