SCHEDULE OF SECOND TO FOURTEENTH FLOOR BEAMS

BEAM NUMBERS	SIZE		BOTTOM REINFORCEMENT			TOP REINFORCEMENT			SHEAR STIRRUPS			REMARKS
	B	D	LEFT	MID SPAN	RIGHT	LEFT	MID SPAN	RIGHT	LEFT	MID SPAN	RIGHT	
B1,B97	280	340	2-Y20	2-Y20	2-Y20	2-Y12	2-Y12	2-Y12 +2-Y20	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	T.O.C. -60MM
B2,B98	280	340	2-Y20	2-Y20	2-Y20	2-Y12 +2-Y20	2-Y12	2-Y12	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	T.O.C. -60MM
B3,B4,B95,B96	200	700	2-Y25 +2-Y20	2-Y25 +2-Y20	2-Y25 +2-Y20	2-Y25 +2-Y25	2-Y20	2-Y25 +2-Y25	2L-Y10@100 C/C	2L-Y10@100 C/C	2L-Y10@100 C/C	–
B3A,B4A,B95A,B96A	200	340	2-Y12	2-Y12	2-Y12	2-Y25	2-Y25	2-Y25	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED T.O.C. -60MM
B5,B6,B93,B94, B9,B10,B89,B90	200	500	2-Y16	2-Y16	2-Y16	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B7,B8,B91,B92	200	500	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B7A,B8A,B91A,B92A	150	500	2-Y12	2-Y12	2-Y12	2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B11,B14,B85,B88	200	700	2-Y16	2-Y16	2-Y16	+2-Y20 +2-Y25	+2-Y20 +2-Y25	+2-Y20 +2-Y25	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B12,B13,B86,B87	200	700	2-Y16	2-Y16 +2-Y12	2-Y16	2-Y20 +2-Y25	2-Y20	2-Y20 +2-Y25	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B16,B17,B82,B83	200	500	+2-Y16 +2-Y12	2-Y16 +2-Y12	2-Y16 +2-Y12	2-Y12 +2-Y16	2-Y12	2-Y12 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B18,B81	200	450	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B19,B21,B78,B80	200	450	2-Y16	2-Y16	2-Y16	2-Y20 +2-Y20	2-Y20	2-Y20 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B20,B79	200	450	2-Y16	2-Y16 +2-Y12	2-Y16	2-Y12 +2-Y20	2-Y12	2-Y12 +2-Y20	2L-Y8@130 C/C	2L-Y8@200 C/C	2L-Y8@130 C/C	–
B22,B23,B28,B29, B70,B71,B76,B77, B24,B27,B72,B75	200	540	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B25,B26,B73,B74	200	500	2-Y16	2-Y16 +2-Y16	2-Y16	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B30,B67	200	450	2-Y12	2-Y12	2-Y12	2-Y20	2-Y20	+2-Y20 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B31,B68	200	450	+2-Y20 +2-Y20	+2-Y20 +2-Y20	+2-Y20 +2-Y20	+2-Y20 +2-Y20	2-Y20	+2-Y20 +2-Y20	2L-Y8@110 C/C	2L-Y8@110 C/C	2L-Y8@120 C/C	–
B32,B69	200	450	2-Y12	2-Y12	2-Y12	+2-Y20 +2-Y20	2-Y20	2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B33,B36,B63,B66	200	700	2-Y16	2-Y16	2-Y16	+2-Y20 +2-Y20	+2-Y20 +2-Y20	+2-Y20 +2-Y20	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B34,B64	200	700	2-Y16	+2-Y16 +2-Y12	2-Y16	+2-Y20 +2-Y20	2-Y20	+2-Y20 +2-Y12	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B35,B65	200	700	2-Y16	+2-Y16 +2-Y12	2-Y16	+2-Y20 +2-Y12	2-Y20	+2-Y20 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B37,B38,B61,B62	200	340	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B39,B57,B42,B60	200	500	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B40,B41,B58,B59	200	340	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	2-Y20	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED T.O.C -60MM
B43,B46,B53,B56	200	700	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	2-Y20	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B44,B54	200	500	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	2-Y20	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B45,B55	200	500	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B47,B51	200	440	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED T.O.C -60MM
B48,B52	200	500	2-Y12	2-Y12	2-Y12	2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	–
B49,B50	200	500	2-Y16	2-Y16	2-Y16	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B99,B106,B191,B194	200	500	2-Y12	2-Y12	2-Y12	2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B100,B105,B192,B193	200	700	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	–
B101,B104,B195,B198	200	700	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y12	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	–
B102,B103,B196,B197	200	500	2-Y12	2-Y12	2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y12	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B107,B108,B109,B110, B187,B188,B189,B190	200	700	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	–
B111,B112,B185,B186	200	540	2-Y16	+2-Y16 +2-Y12	2-Y16	+2-Y12 +2-Y16	2-Y12	+2-Y12 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B113,B114	200	340	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B115,B116,B181,B182	200	700	2-Y16	+2-Y16 +2-Y16	2-Y16	+2-Y16 +2-Y20	2-Y16	+2-Y16 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B117,B118,B179,B180	200	340	2-Y20	2-Y20	2-Y20	+2-Y25 +1-Y25	+2-Y25 +1-Y25	+2-Y25 +1-Y25	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	T.O.C -60MM
B117A,B118A,B179A, B180A	200	340	2-Y20	2-Y20	2-Y20	+2-Y25 +1-Y25	+2-Y25 +1-Y25	+2-Y25 +1-Y25	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED T.O.C -60MM
B119,B174	200	500	2-Y16	2-Y16	2-Y16	+2-Y20 +2-Y20	2-Y20	2-Y20	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B120	200	500	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B121	200	700	+2-Y16 +2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y20	2-Y16	+2-Y16 +2-Y20	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B122	200	500	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y20	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B123,B178	200	500	2-Y16	2-Y16	2-Y16	2-Y20	2-Y20	+2-Y20 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B124,B127,B171,B172	200	500	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B125,B126,B170,B173	200	500	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B128,B167	200	450	2-Y12	2-Y12	2-Y12	2-Y20	2-Y20	+2-Y20 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–

SCHEDULE OF SECOND TO FOURTEENTH FLOOR BEAMS

BEAM NUMBERS	SIZE		BOTTOM REINFORCEMENT			TOP REINFORCEMENT			SHEAR STIRRUPS			REMARKS
	B	D	LEFT	MID SPAN	RIGHT	LEFT	MID SPAN	RIGHT	LEFT	MID SPAN	RIGHT	
B129,B132,B165,B168	200	500	+2-Y12 +1-Y12	+2-Y12 +1-Y12	+2-Y12 +1-Y12	+2-Y16 +1-Y12	+2-Y16 +1-Y12	+2-Y16 +1-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B130,B169	200	450	2-Y12	2-Y12	2-Y12	2-Y25	2-Y25	2-Y25	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B131,B164	200	450	2-Y12	2-Y12	2-Y12	2-Y25	2-Y25	2-Y25	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B133,B166	200	450	2-Y12	2-Y12	2-Y12	2-Y20	2-Y20	+2-Y20 +2-Y16	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B134,B159	200	500	2-Y16	+2-Y16 +2-Y12	2-Y16	+2-Y16 +2-Y20	2-Y16	2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B135,B160	200	340	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	T.O.C -60MM
B136	200	700	+2-Y16 +2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y12	+2-Y16 +2-Y20	2-Y16	+2-Y16 +2-Y20	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B137,B162	200	340	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y16	2-Y16	2-Y16	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B138,B163	200	500	2-Y16	+2-Y16 +2-Y12	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y20	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B139,B140,B157,B158	200	450	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B141,B142,B155,B156	200	340	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B143,B148,B149,B154	200	500	2-Y12	2-Y12	2-Y12	+2-Y16 +2-Y16	+2-Y16 +2-Y16	+2-Y16 +2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	CANTILEVERED
B144,B150	200	500	+2-Y20 +2-Y12	+2-Y20 +2-Y12	+2-Y20 +2-Y12	+2-Y16 +2-Y20	2-Y16	+2-Y16 +2-Y16	2L-Y8@100 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B145,B146,B151,B152	200	340	2-Y12	2-Y12	2-Y12	+2-Y16 +2-Y16	+2-Y16 +2-Y16	+2-Y16 +2-Y16	2L-Y8@100 C/C	2L-Y8@100 C/C	2L-Y8@100 C/C	T.O.C -60MM CANTILEVERED
B147,B153	200	500	+2-Y20 +2-Y12	+2-Y20 +2-Y12	+2-Y20 +2-Y12	+2-Y16 +2-Y20	2-Y16	+2-Y16 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@100 C/C	–
B161	200	700	+2-Y20 +2-Y20	+2-Y20 +2-Y20	+2-Y20 +2-Y20	+2-Y25 +2-Y16	2-Y25	+2-Y25 +2-Y16	2L-Y8@100 C/C	2L-Y8@150 C/C	2L-Y8@100 C/C	–
B175	200	700	2-Y16	2-Y16	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B176	200	700	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y12	2-Y16	+2-Y16 +2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B177	200	700	2-Y16	2-Y16	2-Y16	+2-Y16 +2-Y12	2-Y16	2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	–
B183	200	340	2-Y16	2-Y16	2-Y16	2-Y12	2-Y12	+2-Y12 +2-Y16	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
B184	200	340	2-Y16	2-Y16	2-Y16	+2-Y12 +2-Y16	2-Y12	2-Y12	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@200 C/C	T.O.C -60MM
MB1,MB2	200	700	+2-Y16 +2-Y16	+2-Y16 +2-Y16	+2-Y16 +2-Y16	+2-Y20 +2-Y25	2-Y20	+2-Y20 +2-Y25	2L-Y8@200 C/C	2L-Y8@200 C/C	2L-Y8@180 C/C	MID-LANDING BEAM

KEY PLAN

Shantigram
THE GOOD LIFE

NOTES:
1. ALL DIMENSIONS ARE IN MILLIMETERS AND LVLS IN METERS UNLESS OTHERWISE SPECIFIED
2. PLEASE DO NOT SCALE THE DRAWING.
3. FOLLOW WRITTEN DIMENSION.
4. ALL DIMENSIONS ARE UNFINISHED DIMENSIONS UNLESS OTHERWISE MENTIONED.
5. DISCREPENCIES SHOULD BE BROUGHT TO THE NOTICE OF ARCHITECT / CONSULTANT.
6. THIS DRAWING IS THE PROPERTY OF ATRECO AND IS NOT TO BE REPRODUCED, COPIED, HANDED OVER TO A THIRD PARTY OR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT HAS BEEN LOANED.

LEGEND :

REVISIONS

Nos.	Revision Description	Date	Revised By
R00	FOR EXECUTION	08.07.21	S.D.K.
R01	AS PER COMMENTS	22.06.21	S.D.K.
R02	AS PER COMMENTS	03.09.21	S.D.K.
R03	REV. AS PER COMMENTS	30.09.21	S.D.K.
R04	REV. AS PER COMMENTS	19.10.21	S.D.K.
R05	REV. AS PER COMMENTS	16.11.21	S.D.K.

PROJECT
R-22 PROJECT AT SHANTIGRAM

CLIENT
adani
Adani Estate Management Private Limited
ATRECO House, CBD, SHANTIGRAM
NR. VAISHNODEVI CIRCLE, S.G.HIGHWAY
AHMEDABAD – 382421 GUJARAT, INDIA

ARCHITECT
GA design
208 ADHYARU INDUSTRIAL ESTATE,
SUNMILL COMPOUND, LOWER PAREL
MUMBAI 400013.
TEL: 24980527, 65049256.
email: projects@gadesign.in

MEP CONSULTANTS
MEPTech
Building Services...Building Confidence...
MEPTECH CONSULTANTS
Address : 904,Supath Building,opp Mc Donald's, 132' Ring Road,Vijay cross Road,Navrangpura, Ahmedabad-380009
Email : info@meptech.in
Web : www.meptech.in
Contact : 079-48011496

LANDSCAPE CONSULTANT
NEWARCH LANDSCAPES LLP
NEWARCH® LANDSCAPES LLP | +91 22 2833 7173 | +91 22 2898 2904 | 8369102789
202-203, Gokarna, R. M. Bhattad Road, Borivali (W), Mumbai - 400092, INDIA.

EPICONS CONSULTANTS PVT. LTD
ARCHITECTURE AND DETAIL ENGINEERING DIVISION
216 A,Amargain Complex, LBS road, khopat, Thane 400 601
ph 91 22 25471144, 25472356, 25475434 www.epicons.co.in

	Name	Sign
Drawn By	R.A.N	
Checked by	S.D.K	
Approved By	A.S.P	

DWG_NO:
N-EMARH06 C150 R05

DWG_TITLE:
SCHEDULE OF SECOND TO FOURTEENTH FLOOR BEAMS

DATE: 16.11.2021

SCALE: 1:100

0 100 200 500 M

N

CAD File No: