SCHEDULE OF RCC BAND BEAMS

BEAM NOS.	BEAM TOP LEVEL	SIZE B	SIZE D	BOTTOM REINFORCEMENT @ LEFT SUPPORT	BOTTOM REINFORCEMENT MID - SPAN	BOTTOM REINFORCEMENT @ RIGHT SUPPORT	TOP REINFORCEMENT @ LEFT SUPPORT	TOP REINFORCEMENT MID - SPAN	TOP REINFORCEMENT @ RIGHT SUPPORT	SIDE FACE REINF. ON EACH FACE	STIRRUPS LEFT SUP. DIA	STIRRUPS LEFT SUP. @c/c	STIRRUPS LEFT SUP. DIST	STIRRUPS CENTRE DIA	STIRRUPS CENTRE @c/c	STIRRUPS RIGHT SUP. DIA	STIRRUPS RIGHT SUP. @c/c	STIRRUPS RIGHT SUP. DIST	BEAM TYPE	REMARKS
BB118	+23.80	2280	550	18-T12	18-T12	18-T12	18-T12 + 8-T12*	18-T12	18-T12 + 8-T12*	-	8L-T8-150								4	-
BB119	+23.80	2280	550	18-T12	18-T12	18-T12	18-T12 + 8-T12*	18-T12	18-T12 + 8-T12*	-	8L-T8-150								4	-
BB120	+23.80	2280	550	18-T12	18-T12	18-T12	18-T12+8-T12 + 8-T12*	18-T12	18-T12 + 14-T12*	-	8L-T8-150								4	-
BB121	+23.80	2280	550	18-T12	8-T12*(0.1L) + 18-T12	18-T12	18-T12 + 14-T12*	18-T12	18-T12	-	8L-T8-150								4	-
BB124	+23.80	2080	550	17-T12	17-T12	17-T12	17-T12	17-T12	17-T12 + 10-T16*	-	7L-T8-150								4	-
BB125	+23.80	2080	550	17-T12	17-T12	17-T12	17-T12 + 10-T16*	17-T12	17-T12 + 6-T12*	-	7L-T8-150								4	-
BB126	+23.80	2080	550	17-T12	17-T12	17-T12	17-T12 + 6-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB127	+23.80	2080	550	17-T12	17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB128	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB129	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 8-T12*	-	7L-T8-150								4	-
BB130	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 8-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB131	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB132	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB133	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 10-T12*	17-T12	17-T12 + 8-T16*	-	7L-T8-150								4	-
BB134	+23.80	2080	550	17-T12	2-T12*(0.1L) + 17-T12	17-T12	17-T12 + 8-T16*	17-T12	17-T12 + 10-T12*	-	7L-T8-150								4	-
BB137	+23.80	1500	550	12-T16	12-T16	12-T16	12-T12	12-T12	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB138	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T16*	12-T12	12-T12	-	6L-T8-175								4	-
BB139	+23.80	1500	550	4-T12* + 12-T12	4-T12* + 12-T12	4-T12* + 12-T12	12-T12	12-T12	12-T12 + 6-T12*	-	6L-T8-175								4	-
BB140	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 6-T12*	12-T12	12-T12 + 8-T12*	-	6L-T8-175								4	-
BB141	+23.80	1500	550	12-T12	4-T12*(0.1L) + 12-T12	12-T12	12-T12 + 8-T12*	12-T12	12-T12 + 8-T12*	-	6L-T8-175								4	-
BB142	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T12*	12-T12	12-T12	-	6L-T8-175								4	-
BB143	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 8-T12*	-	6L-T8-175								4	-
BB144	+23.80	1500	550	12-T12	4-T12*(0.1L) + 12-T12	12-T12	12-T12 + 8-T12*	12-T12	12-T12 + 8-T12*	-	6L-T8-175								4	-
BB145	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T12*	12-T12	12-T12	-	6L-T8-175								4	-
BB150	+23.80	1500	550	4-T12* + 12-T12	4-T12* + 12-T12	4-T12* + 12-T12	12-T12	12-T12	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB151	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T16*	12-T12 + 8-T16*	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB152	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T16*	12-T12	12-T12	-	6L-T8-175								4	-
BB153	+23.80	1500	550	12-T16	2-T16*(0.1L) + 12-T16	12-T16	12-T12	12-T12	12-T12 + 8-T20*	-	6L-T8-175								4	-
BB154	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T20*	12-T12	12-T12	-	6L-T8-175								4	-
BB155	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB156	+23.80	1500	550	4-T12* + 12-T16	4-T12* + 12-T16	4-T12* + 12-T16	12-T12 + 8-T16*	12-T12	12-T12 + 8-T12*	-	6L-T10	115	2300	6L-T8-175					4	-
BB157	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 8-T12*	12-T12	12-T12	-	6L-T8-175								4	-
BB158	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 6-T12*	-	6L-T8-175								4	-
BB159	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 6-T12*	12-T12	12-T12 + 8-T16*	-	6L-T8-175					6L-T8	100	3600	4	-
BB160	+23.80	1500	550	12-T12	2-T12*(0.1L) + 12-T12	12-T12	12-T12 + 8-T16*	12-T12	12-T12 + 4-T12*	-	6L-T8-175					6L-T8	150	2700	4	-
BB161	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 4-T12*	12-T12	12-T12	-	6L-T8	115	1150	6L-T8-175					4	-
BB162	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 2-T12*	-	6L-T8-175								4	-
BB163	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 2-T12*	12-T12	12-T12 + 4-T12*	-	6L-T8-175								4	-
BB164	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 4-T12*	12-T12	12-T12	-	6L-T8-150								4	-
BB165	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB166	+23.80	1500	550	12-T16	2-T16*(0.1L) + 12-T16	12-T16	12-T12 + 8-T16*	12-T12	12-T12	-	6L-T8	125	2000	6L-T8-175					4	-
BB167	+23.80	2000	550	16-T16	16-T16	16-T16	16-T12	16-T12	16-T12 + 14-T25*	-	6L-T8-125								4	-
BB168	+23.80	2000	550	16-T20	8-T16*(0.1L) + 16-T20	16-T20	16-T12 + 14-T25*	16-T12	16-T12	-	6L-T8-125								4	-
BB169	+23.80	2200	550	17-T16	17-T16	17-T16	17-T12	17-T12	17-T12 + 12-T25*	-	7L-T8-140								4	-
BB170	+23.80	2200	550	17-T16	10-T16*(0.1L) + 17-T16	17-T16	17-T12 + 12-T25*	17-T12	17-T12	-	7L-T8-140								4	-
BB171	+23.80	1800	550	15-T20	4-T12*(0.1L) + 15-T20	15-T20	15-T12	15-T12	15-T12 + 10-T20*	-	6L-T8-150					6L-T8	125	1250	4	-
BB171A	+23.80	1800	550	15-T12	15-T12	15-T12	15-T12 + 10-T20*	15-T12	15-T12 + 6-T20*	-	6L-T8-150								4	-
BB172	+23.80	1800	550	15-T16	6-T12*(0.1L) + 15-T16	15-T16	15-T12 + 6-T20*	15-T12	15-T12	-	6L-T8-150								4	-
BB173	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12	12-T12	12-T12 + 8-T12*	-	6L-T8-175								4	-
BB174	+23.80	1500	550	6-T12* + 12-T12	6-T12* + 12-T12	6-T12* + 12-T12	12-T12 + 8-T12*	12-T12	12-T12 + 6-T12*	-	6L-T8-175								4	-
BB175	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12 + 6-T12*	12-T12	12-T12	-	6L-T8-175								4	-
BB176	+23.80	1500	550	12-T12	4-T12*(0.1L) + 12-T12	12-T12	12-T12	12-T12	12-T12 + 8-T16*	-	6L-T8-175								4	-
BB177	+23.80	1500	550	12-T12	6-T16*(0.1L) + 12-T12	12-T12	12-T12 + 8-T16*	12-T12	12-T12 + 4-T12*	-	6L-T8-175								4	-
BB178	+23.80	1500	550	12-T12	12-T12	12-T12	12-T12+4-T12 + 4-T12*	12-T12	12-T12 + 8-T20*	-	6L-T8-175					6L-T10	100	1200	4	-

SCHEDULE OF RCC BAND BEAMS

BEAM NOS.	BEAM TOP LEVEL	SIZE B	SIZE D	BOTTOM REINFORCEMENT @ LEFT SUPPORT	BOTTOM REINFORCEMENT MID - SPAN	BOTTOM REINFORCEMENT @ RIGHT SUPPORT	TOP REINFORCEMENT @ LEFT SUPPORT	TOP REINFORCEMENT MID - SPAN	TOP REINFORCEMENT @ RIGHT SUPPORT	SIDE FACE REINF. ON EACH FACE	STIRRUPS LEFT SUP. DIA	STIRRUPS LEFT SUP. @c/c	STIRRUPS LEFT SUP. DIST	STIRRUPS CENTRE DIA	STIRRUPS CENTRE @c/c	STIRRUPS RIGHT SUP. DIA	STIRRUPS RIGHT SUP. @c/c	STIRRUPS RIGHT SUP. DIST	BEAM TYPE	REMARKS
BB179	+23.80	1500	550	12-T16	4-T16*(0.1L) + 12-T16	12-T16	12-T12 + 8-T20*	12-T12	12-T12	-	6L-T10	100	1200	6L-T8-175					4	-
BB180	+23.80	1800	550	15-T16	4-T12*(0.1L) + 15-T16	15-T16	15-T12	15-T12	15-T12 + 10-T16*	-	6L-T8-150								4	-
BB180A	+23.80	1800	550	15-T12	15-T12	15-T12	15-T12 + 10-T16*	15-T12 + 8-T16*	15-T12 + 8-T16*	-	6L-T8-150								4	-
BB181	+23.80	1800	550	15-T12	10-T12*(0.1L) + 15-T12	15-T12	15-T12 + 8-T16*	15-T12	15-T12	-	6L-T8-150								4	- CANTILEVER BRACK
BKT2	+23.80	500	550	5-T16	5-T16	5-T16	5-T16	5-T16	5-T16	-	3L-T8-100								4	

SCHEDULE OF RCC FRAMING BAND BEAMS

BEAM NOS.	BEAM TOP LEVEL	SIZE B	SIZE D	BOTTOM REINFORCEMENT @ LEFT SUPPORT	BOTTOM REINFORCEMENT MID - SPAN	BOTTOM REINFORCEMENT @ RIGHT SUPPORT	TOP REINFORCEMENT @ LEFT SUPPORT	TOP REINFORCEMENT MID - SPAN	TOP REINFORCEMENT @ RIGHT SUPPORT	SIDE FACE REINF. ON EACH FACE	STIRRUPS LEFT SUP. DIA	STIRRUPS LEFT SUP. @c/c	STIRRUPS LEFT SUP. DIST	STIRRUPS CENTRE DIA	STIRRUPS CENTRE @c/c	STIRRUPS RIGHT SUP. DIA	STIRRUPS RIGHT SUP. @c/c	STIRRUPS RIGHT SUP. DIST	BEAM TYPE	REMARKS
FBB5	+23.80	2880	550	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	-	9L-T8	90	1260	9L-T8	100	9L-T8	90	1260	4	-
FBB6	+23.80	2880	550	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	-	9L-T8	90	1260	9L-T8	125	9L-T8	90	1260	4	-
FBB7	+23.80	2880	550	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	-	9L-T8	90	1260	9L-T8	125	9L-T8	90	1260	4	-
FBB8	+23.80	2880	550	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	-	9L-T8	90	1260	9L-T8	125	9L-T8	90	1260	4	-
FBB8A	+23.80	2880	550	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	16-T16+7-T12	-	9L-T8	100	1100	9L-T8	125	9L-T8	100	1100	4	-
FBB9	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB10	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB11	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB12	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB13	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB14	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	150	6L-T10	100	1100	4	-
FBB15	+23.80	2000	550	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	10-T16+6-T12	-	6L-T10	100	1100	6L-T10	175	6L-T10	100	1100	4	-

NOTE:
A) ALL LONGITUDINAL BARS IN BAND BEAMS ARE PLACED IN ONE LAYER UNLESS OR OTHERWISE SPECIFIED
B) ALL EXTRA BARS TO BE BUNDLED
C) HIGHER DIA. REINFORCMENT TO BE PLACED ON OUTER SIDE OF BEAM WIDTH WHILE LOWER DIA. REINFORCMENT TO BE PLACED ON INNER SIDE OF BEAM WIDTH IN SYMMETRY
D) ALL REINFORCEMENT MARKED WITH '*' ARE EXTRA REINFORCMENT BUNDLED IN SAME LAYER
E) FOR ALL BAND BEAMS REFER TYPICAL DETAILS FROM SHEET 'GPL_BBL-SD-XX-ST-003E'

SCHEDULE OF R.C.C. SLABS

SLAB MARKED	SLAB THICKNESS	BOTTOM REINFORCEMENT ALONG SHORT SPAN (MAIN REINF.)	BOTTOM REINFORCEMENT ALONG LONG SPAN (DISTRIBUTION REINF.)	TOP SUPPORT REINFORCEMENT ALONG SHORT SPAN	TOP SUPPORT REINFORCEMENT ALONG LONG SPAN	IN MID SPAN (TO BE LAPPED WITH SUPPORT REINF.)	DISTRIBUTION	REMARKS
S1	150	T8 - 110 C/C	T8 - 250 C/C	T8 - 230 C/C	T8 - 250 C/C	-	T8 - 270 C/C	ONE WAY
S2	150	T8 - 130 C/C	T8 - 230 C/C	T8 - 200 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S3	200	T10 - 130 C/C	T8 - 140 C/C	T8 - 170 C/C	T8 - 200 C/C	T8 - 250 C/C	T8 - 200 C/C	TWO WAY
S4	150	T8 - 230 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S5	150	T8 - 250 C/C	T8 - 250 C/C	-	-	-	T8 - 270 C/C	TWO WAY
S6	150	T8 - 210 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	ONE WAY
S7	150	T8 - 250 C/C	T8 - 250 C/C	-	-	-	T8 - 270 C/C	ONE WAY
S8	150	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S9	175	T10 - 120 C/C	T8 - 150 C/C	T8 - 140 C/C	T8 - 230 C/C	-	T8 - 230 C/C	TWO WAY
S10	175	T10 - 120 C/C	T8 - 150 C/C	T8 - 140 C/C	T8 - 230 C/C	-	T8 - 230 C/C	TWO WAY
S11	175	T10 - 130 C/C	T8 - 150 C/C	T8 - 140 C/C	T8 - 230 C/C	-	T8 - 230 C/C	TWO WAY
S11A	175	T10 - 130 C/C + T8 - 200 C/C	T8 - 150 C/C	T8 - 140 C/C + T8 - 280 C/C	T8 - 230 C/C	-	T8 - 230 C/C	TWO WAY
S12	150	T8 - 250 C/C	T8 - 250 C/C	-	-	-	T8 - 270 C/C	ONE WAY
S13	150	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S14	150	T8 - 100 C/C	T8 - 170 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S15	150	T8 - 100 C/C	T8 - 200 C/C	T8 - 260 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S16	150	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S17	150	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S18	150	T10 - 120 C/C	T8 - 160 C/C	T8 - 160 C/C	T8 - 220 C/C	-	T8 - 270 C/C	TWO WAY
S19	175	T10 - 130 C/C	T8 - 230 C/C	T8 - 170 C/C	T8 - 230 C/C	-	T8 - 230 C/C	ONE WAY
S20	200	T10 - 120 C/C	T8 - 200 C/C	T8 - 180 C/C	T8 - 200 C/C	T8 - 250 C/C	T8 - 200 C/C	ONE WAY
S21	150	T8 - 180 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S22	150	T8 - 150 C/C	T8 - 260 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S23	150	T8 - 140 C/C	T8 - 230 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S24	230	T12 - 115 C/C	T12 - 115 C/C	T8 - 115 C/C	T8 - 115 C/C	T8 - 115 C/C	T8 - 200 C/C	TWO WAY
S25	150	T8 - 160 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S26	200	T10 - 100 C/C	T10 - 150 C/C	T8 -100 C/C	T8 - 100 C/C	T8 - 250 C/C	T8 - 270 C/C	TWO WAY
S27	175	T10 - 150 C/C	T8 - 100 C/C	T8 - 175 C/C	T8 - 200 C/C	-	T8 - 270 C/C	TWO WAY
S28	200	T10 - 150 C/C	T10 - 150 C/C	T8 - 200 C/C	T8 - 190 C/C	T8 - 250 C/C	T8 - 270 C/C	TWO WAY
S29	150	T8 - 140 C/C	T8 - 250 C/C	T8 - 250 C/C	T8 - 250 C/C	-	T8 - 270 C/C	TWO WAY
S30	175	T10 - 100 C/C	T10 - 150 C/C	T8 - 150 C/C	T8 - 170 C/C	-	T8 - 270 C/C	TWO WAY
S31	175	T10 - 130 C/C	T8 - 130 C/C	T8 - 170 C/C	T8 - 230 C/C	-	T8 - 270 C/C	TWO WAY
S32	225	T12 - 115 C/C	T12 - 115 C/C	T8 - 100 C/C	T8 - 100 C/C	T8 - 250 C/C	T8 - 270 C/C	TWO WAY
SC1	150	-	T8 - 250 C/C	T8 - 150 C/C (A.B.B.B.)	T8 - 250 C/C	-	T8 - 270 C/C	CANTILEVER SLAB

NOTES:
A) TOP BAR LENGTH AT SUPPORT TO BE L/5
B) AT ANY CONTINUOUS EDGE, HIGHER TOP REINFORCEMENT FROM EITHER SIDE OF SUPPORT TO BE PROVIDED AS TOP CUT-BAR
C) A.B.B.B. REPRESENTS ALTERNATE BARS TO BE BENT BACK

PROVISION :-
LOWER GROUND + GROUND + PD1 TO PD6 +ECO DECK + TERRACE + ROOF

GENERAL NOTES :-
1) READ THIS DRAWING WITH RELEVANT ARCHITECTURAL DRAWINGS
2) IN CASE OF ANY DISCREPANCY KINDLY CONTACT THE DESIGN ENGINEER.
3) REINFORCEMENT GRADE :
FE500 : 8MM & 10MM DIA. BARS
FE550D : 12MM DIA. BARS AND ABOVE
4) CONCRETE GRADE : M40 (ONE GRADE HIGHER TO BE POURED THAN MENTIONED ABOVE)
5) COVER :
BEAMS: 40MM
SLABS (SIMPLY SUPPORTED) = 35MM
SLABS (CONTINOUS) = 30MM
(+5MM EXTRA COVER TO BE ADDED FOR EXPOSED SURFACE AS PER GPL MANDATE)
6) Ldt : FE500 :36 DIA.
: FE550D : 40 DIA.
7) REFER GENERAL DETAIL NOTES & DRAWINGS

KEY PLAN:

GENERAL NOTES:
1. THIS DRAWING IS THE COPYRIGHT OF GODREJ PROPERTIES LTD. AND MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE ABOVE CONSULTANT'S AUTHORITY.
2. DO NOT SCALE FROM THE DRAWINGS.
3. ALL DIMENSIONS ARE IN MILLIMETERS AND LEVELS IN METRES UNLESS NOTED OTHERWISE, ALL DIMENSIONS TO BE VERIFIED ON SITE & APPROVED BY THE ENGINEER.
4. THIS DRAWING SHOULD BE CONFIRMED FROM CONTRACTORS.

DRAWING REVISIONS:

No.	Description	Date
R1	BEAM SCHEDULE REVISED	31-05-2025
R2	BEAM SCHEDULE REVISED	18-07-2025
R3	BEAM SCHEDULE REVISED	16-08-2025
R4	BEAM SCHEDULE REVISED	30-08-2025

CLIENT :
GODREJ PROPERTIES LTD. | PROPERTIES

ARCHITECTURAL CONSULTANT :
KAPADIA & ASSOCIATED PVT. LTD.

MEPF CONSULTANT :
AEON Integrated Building Design Consultants LLP

LANDSCAPE CONSULTANT:

STRUCTURAL CONSULTANT :
Gokani Consultants and Engineers LLP
801 Quantum Tower, Rambaug Lane,
off S.V.Road, Chincholi, Malad (West),
Mumbai 400 064, India. T: +91 22 2888 4400
ww.gokaniconsultants.com
email : info@gokaniconsultants.com

BIM CONSULTANT :

PROJECT TITLE:
Godrej - Big Bull

NORTH:

DRAWING TITLE:
BAND BEAM & SLAB SCHEDULE AT 1ST PODIUM FLOOR (NON-TOWER)

PROJECT CODE:	PHASE:	SCALE:	DATE:
GPL_BBL		@A1	31/05/2025
DRAWN BY:	**DESIGNED BY:**	**CHECKED BY:**	**APPROVED BY:**
AV	SG	SB	VG

STAMP, SIGN & DATE:

STRUCTURAL CONSULTANT:	MEPF CONSULTANT :	LANDSCAPE CONSULTANT:	ARCHITECTURAL CONSULTANT:

ISSUED FOR: ☐ CONCEPT ☐ APPROVAL ☐ SD ☐ TENDER ☐ DD ☐ SHOP DRAWING ■ GFC ☐ AS-BUILT

DRAWING NUMBER:
GPL_BBL-NTA-P1-ST-603
GOKANI DRAWING NUMBER:
948-NTA-P1-14-R4

REVISION:
R4